

**QUESTIONS AND ANSWERS REGARDING
MSCAA PROJECT 08-1260-05
Glycol Management Program – Control Facility - Construction**

1.	<ol style="list-style-type: none">1. In Section 12 24 13, Part 2 says Cradle to Cradle certified. Then on Basis of Design and drawings says Mecho Soho but Soho fabric is not Cradle to Cradle. Could you confirm the type of fabric needed?2. Can the mounting be in the center of the mullions? The specs say in 2.02 B Mounting: Window Jamb Mounting.
	<ol style="list-style-type: none">1. Mecho Soho is acceptable. Cradle to Cradle is not required.2. Window Jamb Mounting is required.
2.	Would it be possible to get the AutoCAD files of the Grading and Drainage Plans, for estimating purposes? Please advise.
	Cad files will not be provided prior to award.
3.	See submitted panel substitution requests. Your prompt review and approval is requested for the attached product substitutions on the above referenced project.
	Substitutions requests will be reviewed once under contract.
4.	<ol style="list-style-type: none">1. Referencing electrical drawing, E1.3 electrical one-line diagram.<ol style="list-style-type: none">a. Can you confirm that the generator and Future Tenant UPS will be excluded from this bid?b. Please confirm that Panel P5 will be fed from Panel P1, in lieu of Future UPS?
	<ol style="list-style-type: none">a. Generator is <u>NOT</u> part of this bid. UPS-1 is a 30KVA device required in this bid. Plan revision to reflect this forthcoming in Addendum 2.b. P5 will be fed from the UPS.

5.	Will we be required to use Schneider electric for access controls installation as on previous airport projects?
	Yes. Contractor shall use Schneider Electric for access controls installation and commissioning. This information will be added to plans/specs issued in Addendum 2. Contact Kenneth Kendra of Schneider Electric at 919-463-3317 or ken.kendra@schneiderelectric.com to coordinate the access control system work.
6.	Will we be required to use JCI for building integration?
	Yes. Contractor shall use JCI for required integration with existing Building Automation System.
7.	Will a simplex fire alarm system be required as on other airport projects?
	Yes. As part of this project contractor will be required to furnish and install a complete addressable type fire alarm system in compliance with ADA requirements as manufactured by Simplex True Alarm Series 4100ES. (No other manufacturer's will be considered). Additional information will be added to plan/specs issued in Addendum 2.

**Questions are listed as submitted, company names are withheld.
This Addendum No. 2 includes Questions received through July 16, 2021.
Questions after this date will be answered in a future Addendum.**