

EAST PERIMETER VEHICLE SERVICE ROAD REHAB MEMPHIS INTERNATIONAL AIRPORT

MEMPHIS-SHELBY COUNTY AIRPORT AUTHORITY MEMPHIS, TN MSCAA PROJECT #: #23-1476-10

UTILITY AND EMERGENCY TELEPHONE NUMBERS

MEMPHIS-SHELBY COUNTY AIRPORT AUTHORITY (MSCAA) - MEMPHIS, TENNESSEE

EMERGENCIES AIRPORT COMMUNICATION CENTER MSCAA OPERATIONS FAA AIR TRAFFIC CONTROL TOWER TENNESSE CALL BEFORE YOU DIG (BUD) (901) 922-8333 (901) 922-8298 (901) 922-8117 (901) 842-8400 811

OWNER CONTACT INFORMATION

BRIAN TENKHOFF, PE DIRECTOR OF DEVELOPMENT MEMPHIS SHELBY COUNTY AIRPORT AUTHORITY (MSCAA) 2491 WINCHESTER ROAD, SUITE 113 MEMPHIS, TN 36116-3856 (901) 922-2297

ENGINEER CONTACT INFORMATION

JOSH MANN, PE - LEAD CIVIL ENGINEER FOTH INFRASTRUCTURE & ENVIRONMENT, LLC 5100 POPLAR AVENUE CLARK TOWER, SUITE 2709A MEMPHIS, TN 38137 (515) 322-0069

PROPERTY ADDRESS

MEMPHIS INTERNATIONAL AIRPORT 2491 WINCHESTER ROAD MEMPHIS, TENNESSEE 38116

UTILITY NOTES

WHERE PUBLIC UTILITY FIXTURES ARE SHOWN AS EXISTING ON THE PLANS OR ENCOUNTERED WITHIN THE CONSTRUCTION AREA, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE OWNERS OF THOSE UTILITIES PRIOR TO THE BEGINNING OF ANY CONSTRUCTION. THE CONTRACTOR SHALL AFFORD ACCESS TO THESE FACILITIES FOR NECESSARY MODIFICATION OF SERVICES. UNDERGROUND FACILITIES, STRUCTURES AND UTILITIES HAVE BEEN PLOTTED FROM AVAILABLE SURVEYS AND RECORDS, AND THEREFORE THEIR LOCATIONS MUST BE CONSIDERED APPROXIMATE ONLY. IT IS POSSIBLE THERE MAY BE OTHERS, THE EXISTENCE OF WHICH PRESENTLY NOT KNOWN OR SHOWN. IT IS THE CONTRACTOR'S RESPONSIBLITY TO DETERMINE THEIR EXISTENCE AND EXACT LOCATION AND TO AVOID DAMAGE THERETO. NO CLAIMS FOR ADDITIONAL COMPENSATION WILL BE ALLOWED TO THE CONTRACTOR FOR ANY INTERFERENCE OR DELAY CAUSED BY SUCH WORK.

THE CONTRACTOR IS REQUIRED TO UTILIZE THE UTILITY ONE-CALL SERVICE AT (800) 351-1111 AT LEAST 48 HOURS PRIOR TO EXCAVATING ANYWHERE ON THE PROJECT. THE CONTRACTOR MUST ALSO CONTACT THE AIRPORT AND THE FAA AT LEAST 48 HOURS IN ADVANCE FOR LOCATES.

UTILITY CONFLICTS DISCOVERED DURING CONSTRUCTION WILL BE ADDRESSED AT THE TIME OF DISCOVERY.

Ζ 0 - \mathbf{m} Ш 2 AIRPOR O M AL \mathbf{O} TION, R 4 ERN, S Ζ MEMPHIS C Т 2 ш PERIME S Ш

10

0024M300.

*



Foth

<form> • CONTROLICION • CONTROLICION NELTINA SPETINA PHASINONO PHASE 1 • COLORITICUITION NELTINA SPETINA PHASINONO PHASE</form>			*
INDEX OF SHEET ************************************	ΗΔ	ΒΙΙ ΙΤΔΤΙΟΝ	1.00
<form></form>			#: GI
Image: Description of the sector of the s			IEET
If B PLANS APRIL 8, 2025 1			SH
APRIL 8, 2025 INDEX OF SHEETS HET TILE COLSPANE"S SHEET TILE COLSPANE"S SHEET TILE COLSPANE"S SHEET CONTROL PLAN COLSPANE"S SHEET CONTROL PLAN COLSPANE"S SHEET CONTROL PLAN COLSPANE"S SHEET A PHASING - OVERVEWS COLSPANE"S PLANSING - PHASE 1 COLSPANE"S PLAN PAVING DETAILS PAVING DETAILS COLSPANE"S PLAN PAVING DETAILS PAVING DETAILS PAVING DETAILS PAVING DETAILS PAVING DETAILS PAVING PLAN		IFB PLANS	*
INDEX OF SHEETS NEET TITLE GET NUMBER SHEET TITLE GET 00 FITLE SHEET GET 00 CONSTRUCTION SAFETY & PHASING - NOTES GC2.00 CONSTRUCTION SAFETY & PHASING - NOTES GC2.01 CONSTRUCTION SAFETY & PHASING - PHASE 1 GC2.02 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2.03 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2.04 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2.05 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2.04 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2.05 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2.04 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2.05 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2.06 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2.07 PANINE PLAN CP1.02 PANINE PLAN CP1.02 PANINE PLAN CP2.01 PANINE PLAN CM1.01 PAVEMENT MARKING CLAILS CM1.01 PAVEMENT MARKING CLAILS CM1.01 PAVEMENT MARKING CLAILS JOSH MANN, PR JOSH MANN, PR License Muniber: <th></th> <th>APRIL 8, 2025</th> <th></th>		APRIL 8, 2025	
INDEX OF SHEETS INDEX OF SHEET ITLE 01:00 TTTE SHEET SHEET ITTLE SHEE		•	
HELT NUMBER SHEET ITTLE Itel Support G1:00 TITLE SHEET SUMMARY OF QUANTITIES G1:01 SUMMARY OF QUANTITIES SUMMARY OF QUANTITIES G1:02 CONSTRUCTION SAFETY & PHASING - NOTES CONSTRUCTION SAFETY & PHASING - OVERVIEW GC2:01 CONSTRUCTION SAFETY & PHASING - PHASE 1 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC2:02 CONSTRUCTION SAFETY & PHASING - PHASE 3 COLOR GC2:03 CONSTRUCTION SAFETY & PHASING - PHASE 4 COLOR GC2:04 CONSTRUCTION SAFETY & PHASING - DETAILS COLOR C0:01 DEMOUTION PLAN POPILE CP1:01 PAVINO PLAN POPILE CP2:01 PAVINO PLAN POPILE CP2:01 PAVINO PLAN COLONTROL DETAILS CM1:01 PAVEMENT MARKING PLALS COLOR CM2:01 PAVINE PLAN COLOR CM2:01 PAVINE PLAN COLONTROL DETAILS CM2:01 PAVEMENT MARKING PLALS COLOR		INDEX OF SHEETS	ORT
OTTO: SUMMARY OF QUANTITIES GL:00 PROJECT OVERVIEW & SURVEY CONTROL PLAN GC:01 CONSTRUCTION SAFETY & PHASING - NOTES GC:02 CONSTRUCTION SAFETY & PHASING - PHASE 1 GC:02 CONSTRUCTION SAFETY & PHASING - PHASE 2 GC:04 CONSTRUCTION SAFETY & PHASING - PHASE 3 GC:05 CONSTRUCTION SAFETY & PHASING - PHASE 3 GC:04 CONSTRUCTION SAFETY & PHASING - PHASE 3 GC:05 CONSTRUCTION SAFETY & PHASING - PHASE 3 GC:04 CONSTRUCTION SAFETY & PHASING - PHASE 3 GC:05 CONSTRUCTION SAFETY & PHASING - PHASE 3 GC:04 CONSTRUCTION SAFETY & PHASING - DETAILS CP1:01 PAVING PLAN CP2:02 LROSION CONTROL DETAILS CM1:01 PAVEMENT MARKING DETAILS CM2:01 PAVEMENT MARKING DETAILS CM3:01 PAVEMENT MARKING DETAILS CM3:02 <	HEET NUMBER	SHEET TITLE TITLE SHEET	AIRP
GL2.00 PROJECT OVERVIEW & SURVEY CONTROL PLAN Image: Construction SAFETY & PHASING - NOTES GC2.00 CONSTRUCTION SAFETY & PHASING - OVERVIEW Image: Construction SAFETY & PHASING - PHASE 1 GC2.01 CONSTRUCTION SAFETY & PHASING - PHASE 1 Image: Construction SAFETY & PHASING - PHASE 3 GC2.02 CONSTRUCTION SAFETY & PHASING - PHASE 3 Image: Construction SAFETY & PHASING - PHASE 3 GC2.01 CONSTRUCTION SAFETY & PHASING - DETAILS Image: Construction SAFETY & PHASING - DETAILS CD1.01 DEMOLITION PLAN Image: Construction SAFETY & PHASING - DETAILS Image: Construction SAFETY & PHASING - DETAILS CP1.02 PAVING PLAN Image: Construction SAFETY & PHASING - DETAILS Image: Construction SAFETY & PHASING - DETAILS CP1.02 PAVING PLAN Image: Construction SAFETY & PHASING - DETAILS Image: Construction SAFETY & PHASING - DETAILS CM1.01 PAVEMENT MARKING DETAILS Image: Construction SAFETY & PHASING - DETAILS Image: Construction SAFETY & PHASING - DETAILS CM2.01 PAVEMENT MARKING DETAILS Image: Construction SAFETY & PHASING - DETAILS Image: Construction SAFETY & PHASING - DETAILS CM2.01 PAVEMENT MARKING DETAILS Image: Construction SAFETY & PHASING - DETAILS Image: Construction SAFETY & PHASING - DETAILS CM2.01 PAVEMENT MARKING DETAILS Image: Construction SAFETY & PHASING - DETAILS Image: Construction SAFETY & PHASING - DETAILS <td>GI1.00</td> <td>SUMMARY OF QUANTITIES</td> <td>VAL</td>	GI1.00	SUMMARY OF QUANTITIES	VAL
CUI-101 CONSTRUCTION SAFETY & PHASING - OVERVEW CONSTRUCTION SAFETY & PHASING - PHASE 1 CONSTRUCTION SAFETY & PHASING - PHASE 2 CONSTRUCTION SAFETY & PHASING - PHASE 3 CONSTRUCTION SAFETY & PHASING - PHASE 3 CONSTRUCTION SAFETY & PHASING - PHASE 3 CONSTRUCTION SAFETY & PHASING - PHASE 4 CONSTRUCTION SAFETY & PHASING - PHASE 3 CONSTRUCTION SAFETY & PHASING - PHASE 4 CONSTRUCTION SAFETY & PHASING - PHASE 3 CONSTRUCTION SAFETY & PHASING - PHASE 4 CONSTRUCTION	GI2.00	PROJECT OVERVIEW & SURVEY CONTROL PLAN	TIOI
GC2.11 CONSTRUCTION SAFETY & PHASING - PHASE 1 GC2.02 CONSTRUCTION SAFETY & PHASING - PHASE 3 GC2.03 CONSTRUCTION SAFETY & PHASING - PHASE 3 GC2.04 CONSTRUCTION SAFETY & PHASING - PHASE 4 GC3.01 CONSTRUCTION SAFETY & PHASING - PHASE 3 GC4.02 CONSTRUCTION SAFETY & PHASING - PHASE 4 GC3.01 CONSTRUCTION SAFETY & PHASING - PHASE 4 GC4.01 DEMOLITION PLAN CP1.02 PAVING PLAN CP2.01 PAVING DETAILS CM2.01 PAVEMENT MARKING DETAILS CM2.01 PAVEMENT MARKING DETAILS CM2.01 PAVEMENT MARKING DETAILS JOSH MANN, PE JOSH MANN, PE License Number: JOSH MANN, PE	GC2.00	CONSTRUCTION SAFETY & PHASING - NOTES	RNA
GG2.02 CONSTRUCTION SAFETY & PHASING - PHASE 2 GG2.03 CONSTRUCTION SAFETY & PHASING - PHASE 3 GG2.03 CONSTRUCTION SAFETY & PHASING - PHASE 4 GG3.01 CONSTRUCTION SAFETY & PHASING - DETAILS CONSTRUCTION SAFETY & PHASING - DETAILS C01.01 DEMOLITION PLAN PAVING PLAN PHAVING PLAN PHAVING PLAN CP1.02 PAVING PLAN PAVING PLAN PHAVING PLAN PHAVING PLAN CP2.02 EROSION CONTROL DETAILS CM.01 PAVEMENT MARKING PLAN CM.01 PAVEMENT MARKING PLAN CM.01 CM2.01 PAVEMENT MARKING DETAILS CM.01 PAVEMENT MARKING DETAILS CM.01 PAVEMENT MARKING DETAILS CM.01 CM2.01 PAVEMENT MARKING DETAILS CM.01 PAVEMENT MARKING DETAILS CM.01 PAVEMENT MARKING DETAILS CM.01 CM2.01 PAVEMENT MARKING DETAILS CM.01 PAVEMENT MARKING DETAILS CM.01 PAVEMENT MARKING DETAILS CM.01 CM.01 PAVEMENT MARKING DETAILS CM.01 CM.01 <td< td=""><td>GC2.01</td><td>CONSTRUCTION SAFETY & PHASING - PHASE 1</td><td>NTE</td></td<>	GC2.01	CONSTRUCTION SAFETY & PHASING - PHASE 1	NTE
GC2.04 CONSTRUCTION SAFETY & PHASING - PHASE 4 GC3.01 CONSTRUCTION SAFETY & PHASING - DETAILS GC3.01 PAVEMENT MARKING DETAILS GC3.01 PAVEMENT MARKING DETAILS GC3.01 PAVEMENT MARKING DETAILS GC3.01 PAVEMENT MARKING DETAILS GC3.01 GC3.01 PAVEMENT MARKING DETAILS GC3.01	GC2.02 GC2.03	CONSTRUCTION SAFETY & PHASING - PHASE 2 CONSTRUCTION SAFETY & PHASING - PHASE 3	ISI
GG3.01 CONSTRUCTION SAFETY & PHASING - DETAILS Image: Construction of the constructio	GC2.04	CONSTRUCTION SAFETY & PHASING - PHASE 4	MPI
OLINOT TO THE AN Image: Character and the second secon	GC3.01	CONSTRUCTION SAFETY & PHASING - DETAILS	H الا
CP1.02 PAVING PLAN & PROFILE CP2.02 FOSION CONTROL DETAILS CM2.01 PAVEMENT MARKING PLAN CM2.01 PAVEMENT MARKING DETAILS CM2.01 CM2.01 <td>CP1.01</td> <td>PAVING PLAN</td> <td></td>	CP1.01	PAVING PLAN	
	CP1.02	PAVING PLAN & PROFILE	.
CM1.01 PAVEMENT MARKING PLAN CM2.01 PAVEMENT MARKING DETAILS Image: State of the sta	CP2.01 CP2.02	PAVING DETAILS EROSION CONTROL DETAILS	
CM2.01 PAVEMENT MARKING DETAILS Image: CM2.01 Pavement was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Tennessee. Image: CM2.01 Image: CM2.01 Imag	CM1.01	PAVEMENT MARKING PLAN	
I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Tennessee. Josh MANN, PE License Number: 123332 Pages or sheets covered by this seal: All sheets			MEMPHIS-SHELBY COUNTY AIRPORT
I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Tennessee. Image: Comparison of the State of Tennessee. JOSH MANN, PE License Number: 123332 Pages or sheets covered by this seal: All sheets			*
I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Tennessee. JOSH MANN, PE License Number: 123332 Pages or sheets covered by this seal: All sheets			ENVIRONMENT, LLC
	STEREI SAGRICU STEREI SOLONAL SOLONAL SOLONAL SOLONAL	I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Tennessee. JOSH MANN, PE License Number: 123332 Pages or sheets covered by this seal: All sheets	FOTH INFRASTRUCTURE & E

		SUMMARY OF QUANTITIES - BASE BID			
ITEM NO	SPEC NO	ITEM	LINIT	ΟΠΑΝΤΙΤΆ	
1	A-102-1.1	CONSTRUCTION ACCESS, PROJECT SECURITY, AND STAGING AREA	LS	1	
2	A-102-1.2	MAINTENANCE OF TRAFFIC	LS	1	
3	C-102-5.1	CATCH BASIN PROTECTION (TYPE D)	EA	1	
4	C-105-6.1	MOBILIZATION	LS	1	
5	P-605-5.1	JOINT AND CRACK REPAIR	LF	5,400	
6	P-605-5.2	SEVERE JOINT AND CRACK REPAIR	LF	280	
7	P-620-5.1a	TEMPORARY PAVEMENT MARKING - 6" DOUBLE SOLID YELLOW LINE	LF	1,550	
8	P-620-5.1b	TEMPORARY PAVEMENT MARKING - 6" SINGLE SOLID WHITE LINE	LF	3,098	
9	P-620-5.1c	TEMPORARY PAVEMENT MARKING - 6" SINGLE DASHED WHITE LINE	LF	3,093	
10	P-620-5.2a	PAINTED PAVEMENT MARKING - 6" DOUBLE SOLID YELLOW LINE	LF	1,550	
11	P-620-5.2b	PAINTED PAVEMENT MARKING - 6" SINGLE SOLID WHITE LINE	LF	3,098	
12	P-620-5.2c	PAINTED PAVEMENT MARKING - 6" SINGLE DASHED WHITE LINE	LF	3,093	
13	P-620-5.3a	PAINTED PAVEMENT MARKING - VEHICLE STOP BAR (WHITE)	EA	2	
14	P-620-5.3b	PAINTED PAVEMENT MARKING - SURFACE PAINTED "STOP" SIGN (RED BACKGROUND WITH WHITE OUTLINE AND LETTERS)	EA	1	
15	TDOT-203.01	ROAD AND DRAINAGE EXCAVATION (UNCLASSIFIED)	СҮ	50	
16	TDOT-203.02	UNDERCUTTING	СҮ	350	
17	TDOT-304.01	SELECT MATERIAL (SOIL CEMENT BASE 8" THICK FOR FULL DEPTH REPAIR)	SY	1,045	
18	TDOT-309.01	CEMENT TREATED BASE (8" THICK)	SY	1,045	
19	TDOT-402.01	PRIME COAT	GAL	345	
20	TDOT-403.01	TACK COAT	GAL	125	
21	TDOT-407.01	HOT MIX ASPHALT (HMA) PAVEMENT - BASE COURSE (4.5" THICK) (TDOT 307 Grading B-M PG 70-22)	TN	280	
22	TDOT-411.01	HOT MIX ASPHALT (HMA) PAVEMENT - SURFACE COURSE (2" THICK) (TDOT 411 Grading D PG 70-22)	TN	1,080	
23	TDOT-415.01	2" COLD MILLING	SY	8,990	
24	TDOT-716.01	RAISED PAVEMENT MARKER (TWO SIDED REFLECTOR)	EA	185	

SUMMARY	OF	QUANTITIES	- ADDITIVE	ALTERNATE 1
---------	----	------------	------------	-------------

		SUMMARY OF QUANTITIES - ADDITIVE ALTERNATE 1			
					AS-BUILT
ITEM NO.	SPEC. NO.	ITEM	UNIT	QUANTITY	QUANTITY
1	A-102-1.1	CONSTRUCTION ACCESS, PROJECT SECURITY, AND STAGING AREA	LS	1	
2	A-102-1.2	MAINTENANCE OF TRAFFIC	LS	1	
3	C-105-6.1	MOBILIZATION	LS	1	
4	P-605-5.1	JOINT AND CRACK REPAIR	LF	2,225	
5	P-605-5.2	SEVERE JOINT AND CRACK REPAIR	LF	120	
6	P-620-5.1a	TEMPORARY PAVEMENT MARKING - 6" DOUBLE SOLID YELLOW LINE	LF	2,830	
7	P-620-5.1b	TEMPORARY PAVEMENT MARKING - 6" SINGLE SOLID WHITE LINE	LF	1,307	
8	P-620-5.1c	TEMPORARY PAVEMENT MARKING - 6" SINGLE DASHED WHITE LINE	LF	1,067	
9	P-620-5.2a	PAINTED PAVEMENT MARKING - 6" DOUBLE SOLID YELLOW LINE	LF	2,830	
10	P-620-5.2b	PAINTED PAVEMENT MARKING - 6" SINGLE SOLID WHITE LINE	LF	1,307	
11	P-620-5.2c	PAINTED PAVEMENT MARKING - 6" SINGLE DASHED WHITE LINE	LF	1,067	
12	P-620-5.3a	PAINTED PAVEMENT MARKING - VEHICLE STOP BAR (WHITE)	EA	1	
13	P-620-5.3b	PAINTED PAVEMENT MARKING - SURFACE PAINTED "STOP" SIGN (RED BACKGROUND WITH WHITE OUTLINE AND LETTERS)	EA	1	
14	P-620-5.4	PAINTED PAVEMENT MARKING - FAA MOVEMENT/NON-MOVEMENT MARKING	SF	154	
15	TDOT-203.01	ROAD AND DRAINAGE EXCAVATION (UNCLASSIFIED)	СҮ	50	
16	TDOT-203.02	UNDERCUTTING	СҮ	70	
17	TDOT-304.01	SELECT MATERIAL (SOIL CEMENT BASE 8" THICK FOR FULL DEPTH REPAIR)	SY	200	
18	TDOT-309.01	CEMENT TREATED BASE (8" THICK)	SY	200	
19	TDOT-402.01	PRIME COAT	GAL	67	
20	TDOT-403.01	TACK COAT	GAL	25	
21	TDOT-407.01	HOT MIX ASPHALT (HMA) PAVEMENT - BASE COURSE (4.5" THICK) (TDOT 307 Grading B-M PG 70-22)	TN	55	
22	TDOT-411.01	HOT MIX ASPHALT (HMA) PAVEMENT - SURFACE COURSE (2" THICK) (TDOT 411 Grading D PG 70-22)	TN	545	
23	TDOT-415.01	2" COLD MILLING	SY	4,580	
24	TDOT-716.01	RAISED PAVEMENT MARKER (TWO SIDED REFLECTOR)	EA	75	





VSR CENTERLINE DATA									
	SEGMENT	LENGTH	DIRECTION	START STATION	START NORTHING	START EASTING	END STATION	END NORTHING	END EAS
	L1	93.978	S85° 43' 53.86"E	100+00.00	N: 286823.7306	E: 784946.7496	100+93.98	N: 286823.7306	E: 785040
	L2	225.020	S89° 12' 25.45"E	100+93.98	N: 286816.7360	E: 785040.4670	103+19.00	N: 286816.7360	E: 78526
	C1	714.305	N67° 31' 45.79"E	103+19.00	N: 286813.6220	E: 785265.4650	110+33.30	N: 286813.6220	E: 785907
	C2	556.174	N24° 01' 27.56"E	110+33.30	N: 287079.2857	E: 785907.7655	115+89.48	N: 287079.2857	E: 786129
	L3	186.652	N03° 40' 29.79"E	115+89.48	N: 287577.4801	E: 786129.8294	117+76.13	N: 287577.4801	E: 78614
	C3	317.444	N18° 55' 25.21"W	117+76.13	N: 287763.7480	E: 786141.7930	120+93.57	N: 287763.7480	E: 78604 ⁻
	L4	206.427	N43° 58' 21.63"W	120+93.57	N: 288056.4080	E: 786041.4580	123+00.00	N: 288056.4080	E: 785898

				PREP		<u>.</u>	TAKEO	ŦWITH	łUs
				چ				RPO	5 RT
	0 scale	100 200 feet		PREP	ARED BY:	Fo	t	h	
	L	EGEND		KEY N	IAP:				
EXISTING	PROPOSED	PAVEMENT - ASPHALT (BASE BID)							
		PAVEMENT - ASPHALT (ADD. ALT. 1)						1 //	
08080	N/A	RIPRAP							
RSA	N/A	RUNWAY SAFETY AREA						X	XIX
— ROFA ———	N/A	RUNWAY OBJECT FREE AREA		z			3		
	N/A	TAXIWAY SAFETY AREA		REVISION DESCRIPTION					
— TOFA ———	N/A	TAXIWAY OBJECT FREE AREA							
	N/A	LOC/ILS CRITICAL AREA		TEB					
SA SAN	N/A	SANITARY SEWER		DA DA					
ST STM	N/A	STORM SEWER		0 Z					
≶ w	N/A	WATER							
)	N/A	ELECTRICAL - AIRFIELD CIRCUIT							
UGE	N/A	ELECTRICAL - UNDERGROUND CABLE							
		PAVEMENT MARKINGS		SOAD	ORT		. 2	2	
CP#	∠A ^{CP#}	CONTROL POINT		RVICE F	L AIRP(ζ] -	
N/A		ALIGNMENT			IS, TN				
ES: CONTRACT POINTS, AN PROJECT D CONTRACT ELEVATION	FOR SHALL PROTE ND BENCHMARKS DATUM NAD83, TE FOR SHALL VERIFY NS PRIOR TO CONS	ECT SURVEY MONUMENTS, REFERENC DURING CONSTRUCTION. NNESSEE US SURVEY FOOT. CONTROL POINT LOCATIONS AND STRUCTION.	E		MEMPHIS INTERNA MEMPH				



	TAXIWAY SAFETY AREA INFORMATION									
AXIWAY	XIWAY ADG WIDTH TSA TOFA									
А	V	75FT	214FT	285FT						

GENERAL SAFETY AND PHASING NOTES:

THE CONTRACTOR SHALL COMPLY WITH THE FOLLOWING PROVISIONS. NO DIRECT PAYMENT FOR THIS WORK WILL BE MADE EXCEPT FOR WHE PLANS AND/OR SPECIFICATIONS. ALL COSTS FOR MATERIAL, LABOR, EQUIPMENT, ETC., TO COMPLY WITH THESE PROVISIONS SHALL BE CONSID PROJECT.

GENERAL

1. UTILITY AND EMERGENCY TELEPHONE NUMBERS

-	EMERGENCY:	(901) 922-8333
-	TENNESSEE ONE-CALL:	(800) 351-1111
-	MSCAA COMMUNICATION/NON-EMERGENCY	(901) 922-8298
-	MSCAA AIRPORT OPERATIONS CENTER	(901) 922-8117

- 2. IN THE EVENT OF A MEDICAL OR POLICE EMERGENCY, THE CONTRACTOR SHALL CALL AIRPORT POLICE FIRST, (901) 922-8333, AND THE AI IMMEDIATELY THEREAFTER. THE OPERATIONS CENTER WILL COORDINATE ANY EMERGENCY RESPONSE.
- 3. IN THE EVENT OF A DECLARED AIRCRAFT EMERGENCY, AIRPORT OPERATIONS PERSONNEL MAY REQUEST THE CONTRACTOR TO TEMPORA VACATE THE PREMISE UNTIL THE EMERGENCY EVENT IS SATISFACTORILY ADDRESSED.
- 4. IN THE EVENT OF A DECLARED SEVERE WEATHER EVENT, INCLUDING AN EVENT REQUIRING LOW VISIBILITY OPERATIONS/SURFACE MOVEN SYSTEM (LVO/SMGCS) PROCEDURES, AIRPORT OPERATIONS PERSONNEL MAY REQUEST THE CONTRACTOR TEMPORARILY SUSPEND OPER PREMISE UNTIL THE EVENT IS OVER.
- NO SMOKING IS ALLOWED WITHIN THE RESTRICTED AREAS OF THE AIRPORT. NO OPEN FLAMES ALLOWED EXCEPT BY SPECIAL PERMISSIO OPERATIONS/PROGRAM MANAGER PERSONNEL. WORK ASSOCIATED WITH TAR KETTLES TO MELT JOINT SEALANT SHALL REMAIN A MINII FUEL VEHICLES.
- 6. THE AIR OPERATIONS AREA (AOA), CONSISTS OF ALL AREAS OF THE AIRPORT LOCATED WITHIN THE PERIMETER SECURITY FENCE. THE CO PROJECT ENGINEER AT LEAST 48 HOURS PRIOR TO ANY WORK ON THIS PROJECT.
- 7. THE CONTRACTOR SHALL COORDINATE ALL OPERATIONS WITH THE MSCAA PROJECT ENGINEER AND SHALL SUBMIT A PROPOSED SCHED PRE-CONSTRUCTION MEETING. REFER TO THE MSCAA FRONT ENDS FOR ADDITIONAL INFORMATION..
- 8. ALL WASTE AND REMOVED ITEMS SHALL BECOME PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED FROM THE AIRPORT AND DI-OFFSITE, UNLESS OTHERWISE NOTED IN THE PLANS.
- 9. ALL UNDERGROUND STRUCTURES (MANHOLES, CATCH BASINS, ETC) ARE CONSIDERED CONFINED SPACE ENTRY. THE CONTRACTOR SHAL AND COMPLETE THE REQUIRED PERMITS FOR CONFINED SPACE ENTRY.
- 10. IN THE EVENT OF NIGHT TIME OPERATIONS, THE CONTRACTOR MUST SHIELD ALL FLOOD LIGHTS, KEEP LIGHTS POINTED AWAY FROM THE DEPARTING AIRCRAFT.
- 11. THE AIRPORT MAY TEMPORARILY SUSPEND CONTRACTOR OPERATIONS IN CERTAIN AREAS TO ADDRESS EMERGENCIES.
- 12. THE PROJECT PHASING PLAN DOES NOT RELIEVE THE CONTRACTOR FROM FOLLOWING OSHA/TOSHA SAFETY REQUIREMENTS.
- 13. CONTRACTOR IS RESPONSIBLE FOR THE ACTIONS OF THEIR EMPLOYEES AS WELL AS THE ACTIONS OF THEIR SUB-CONTRACTOR'S EMPLOYEES HALL ALSO MEAN THE REQUIREMENT EXTENDS TO THE SUB-CONTRACTOR'S EMPLOYEES.
- 14. CONTRACTOR SHALL COORDINATE ANY CRANE USAGE AND ALL EQUIPMENT OVER 20' WITH MSCAA 45 DAYS IN ADVANCE. IF CONTRACTO THE CONTRACTOR IS REQUIRED TO SUBMIT FAA FORM 7460 REGARDING CONSTRUCTION EQUIPMENT HEIGHT AND OBTAIN APPROVAL PR WORK ASSOCIATED WITH THIS EQUIPMENT. SUBMITTAL REVIEW A RECEIVING A RESPONSE FROM THE FAA TYPICALLY TAKES 60-90 DAYS NOT ALWAYS GUARANTEED.

COORDINATION

- 1. WEEKLY CONSTRUCTION PROGRESS MEETINGS WILL BE HELD THROUGHOUT THE DURATION OF THE PROJECT. AT A MINIMUM, REQUIRED SUPERINTENDENT AND FOREMAN OF PRIME CONTRACTOR, AS WELL AS THE PROJECT FOREMAN FOR EACH SUBCONTRACTOR WITH WORK PERIOD. CONSTRUCTION PHASING AND SAFETY WILL BE A STANDING AGENDA ITEM AT THE WEEKLY CONSTRUCTION PROGRESS MEETING
- 2. THE CONTRACTOR SHALL PROVIDE, PRIOR TO START OF CONSTRUCTION, THE NAME(S) AND 24 HOUR CONTACT PHONE NUMBERS OF THE CHARGE.
- 3. AT ALL TIMES WHEN CONSTRUCTION ACTIVITIES ARE BEING PERFORMED ON THIS PROJECT THE PRIME CONTRACTOR MUST HAVE A FOR AVAILABLE WHO IS AUTHORIZED TO MAKE DECISIONS REGARDING THE OPERATIONS AND SAFETY OF ALL PERSONNEL EMPLOYED BY THE SUBCONTRACTORS. EACH DAY, THE DESIGNATED FOREMAN MUST COORDINATE THEIR ACTIVITIES WITH THE AIRPORT OPERATIONS MAN
- 4. CONTRACTOR SHALL COORDINATE WITH THE MSCAA PROJECT ENGINEER AND MSCAA OPERATIONS MANAGER FOR ALL PAVEMENT CLOS IMPACTING AIRPORT, AIRCRAFT, AND MAINTENANCE OPERATIONS. ADVANCE NOTICE REQUIREMENTS ARE DETAILED ON THE FOLLOWING DOCUMENTS.
- 5. CONTRACTOR SHALL COORDINATE WITH MSCAA AND PROGRAM MANAGER A MINIMUM OF 24 HOURS PRIOR TO THE ISSUANCE OF ALL NO CONSTRUCTION. AIRPORT AND FAA SHALL GENERATE AND ISSUE NOTAMS BASED ON CONTRACTOR CONSTRUCTION SCHEDULE AND FAC
- 6. CONTRACTOR MUST PERFORM THIS WORK IN ACCORDANCE WITH THE PROVISIONS INCLUDED WITHIN THE CONTRACT DOCUMENTS.

NAVIGATIONAL AID (NAVAID) FACILITIES

- 1. AIRCRAFT NAVIGATIONAL AIDS (NAVAIDS) PROVIDE VISUAL AND ELECTRONIC INFORMATION WHICH IS USED BY PILOTS WHO OPERATE AND LAND AIRCRAFT AT THE AIRPORT. CONSTRUCTION ACTIVITIES CAN HAVE NEGATIVE IMPACTS ON THE FUNCTIONALITY AND SERVICEABILITY OF NAVAIDS. THE CONTRACTOR MUST COORDINATE THEIR WORK EFFORT AND LIMIT THEIR OPERATIONS SO THAT NAVAIDS ARE NOT IMPACTED.
- 2. CONTRACTOR MUST LIMIT OPERATIONS SO THAT MATERIAL, EQUIPMENT, AND PERSONNEL DO NOT ENTER NAVAID CRITICAL AREAS OR DISTURB POWER TO NAVAID FACILITIES WITHOUT PRIOR COORDINATION WITH THE MSCAA OPERATIONS MANAGER AND MSCAA PROJECT ENGINEER.
- 3. PLANNED NAVAID IMPACTS MUST BE ADDRESSED IN THE CONTRACTORS CONSTRUCTION SCHEDULE. CONTRACTOR IS REQUIRED TO PROVIDE A 45 DAY NOTICE AS WELL AS A MINIMUM 72 HOUR NOTICE TO THE MSCAA OPERATIONS MANAGER AND THE MSCAA PROJECT ENGINEER.

CONTRACTOR ACCESS

- 1. NO CONTRACTOR'S VEHICLES OR PERSONNEL WILL BE ALLOWED TO ENTER ONTO OR CROSS ACTIVE AIRFIELD PAVEMENTS OR THEIR SAFETY AREAS WITHOUT A CLASS 3 ESCORT. INCURSION ONTO OR ACROSS AN ACTIVE RUNWAY, TAXIWAY, OR RUNWAY APPROACHES WITHOUT PRIOR APPROVAL IS A SERIOUS VIOLATION THAT WILL SUBJECT THE CONTRACTOR TO THE MAXIMUM FINE ALLOWED.
- 2. THE CONTRACTOR SHALL MEET THE SECURITY AND ACCESS REQUIREMENTS LISTED IN THE CONTRACT DOCUMENTS. REFER TO CSPP PLANS AND A-102 SPECIFICATION FOR ADDITIONAL INFORMATION.

	CENE	RAL SAFETY AND PHASING NOTES (CONTINUED).
IDERED INCIDENTAL TO THE	3.	OF EACH WORKING DAY, OR AS DIRECTED BY THE MSCAA PROJECT ENGINEER.
	4.	CONTRACTOR SHALL NOT ENTER INTO, OR PLACE STOCKPILES OR STORE MATERIALS AND FUEL IN THE RUNV PRIOR COORDINATION WITH AIRPORT OPERATIONS STAFF. THE GROUND LEVEL PORTION OF THE OBSTACLE I ACTIVE RUNWAY.
	5.	VEHICLES DRIVING ON THE AIRPORT MUST GIVE WAY TO ALL AIRCRAFT. DO NOT DRIVE UNDER AIRCRAFT BOA DRIVE IN A RECKLESS MANNER. REPORT ALL VEHICLE AND AIRCRAFT INCIDENTS, PERSONAL INJURY AND PRO DESIGNATED VEHICLE ROUTES.
	6.	THE CONTRACTOR MUST LIMIT OPERATION OF THEIR EQUIPMENT AND VEHICLES TO THE DEFINED CONSTRUCT CONTRACTOR MUST RELOCATE EQUIPMENT AND VEHICLES FROM THE WORK AREA TO THE STAGING AREA.
AIRPORT OPERATIONS CENTER RARILY SUSPEND OPERATIONS AND	7.	CONTRACTOR ACCESS ONTO THE AOA IS LIMITED TO THE GATES SHOWN ON THE PROJECT SAFETY AND PHA RESTRICTED AREA, EXCEPT AUTHORIZED PERSONNEL AND ESCORTED BY AN APPROPRIATELY BADGED ESCO THE AREAS SHOWN ON THE PROJECT SAFETY AND PHASING PLANS. CONSTRUCTION VEHICLES AND PERSON WITHOUT AN APPROVED ESCORT.
EMENT GUIDANCE AND CONTROL	8.	CONTRACTOR EMPLOYEE PERSONAL VEHICLES MAY NOT BE PARKED OR DRIVEN IN THE AOA. CONTRACTOR WORK AREA WITHIN THE AOA. CONTRACTOR VEHICLES AND EQUIPMENT SHALL BE PARKED NO CLOSER THAI
ION FROM AIRPORT NIMUM OF 50 FEET FROM AIRCRAFT AND	9.	THE PHASING PLAN SHEETS DEPICT HAUL ROUTES AND SITE ACCESS FROM SURROUNDING PUBLIC ROADWAY AIRPORT PERIMETER FENCE. CONTRACTOR ACCESS AND HAULING OPERATIONS ARE STRICTLY LIMITED TO T PERMITS, SIGNAGE, IMPROVEMENTS, AND MAINTENANCE TO HAUL ROUTES AS NEEDED TO EFFICIENTLY PERI THE PLANS. FOLLOWING COMPLETION OF CONSTRUCTION CONTRACTOR IS REQUIRED TO RESTORE HAUL ROU CONDITION.
CONTRACTOR SHALL NOTIFY THE MSCAA	10.	DRIVING PRIVILEGES INSIDE THE AOA ARE LIMITED TO VEHICLES AND PERSONNEL WITH AN OPERATIONAL NE MSCAA BADGING OFFICE. TO DRIVE ON ANY PART OF THE AIRPORT OTHER THAN THE WORK AREAS AS DEFIN FIRST COORDINATE WITH AIRPORT OPERATIONS PERSONNEL. ALL VEHICLES OPERATING OUTSIDE OF THE PR
DISPOSED OF LEGALLY AND PROPERLY	11.	THE PROJECT PLANS SHOW THE ENTRY POINT(S), CONTRACTOR'S STAGING AREA, AND WORK AREA. THE COI CONTRACTOR IS TO PROVIDE TO THE AIRPORT, FOR REVIEW AND APPROVAL, ALL SECURITY MEASURES, BARF OPENINGS BETWEEN THE SECURE AND NON-SECURE AREAS PRIOR TO CREATING THE OPENING. THE AIRPORT
ALL TAKE ALL REQUIRED PRECAUTIONS		BUT THE CONTRACTOR SHOULD NOT RELY ON THE PATROLS TO PROVIDE FULL-TIME SECURITY.
IE ATCT, AND INCOMING AND	12.	IN THE EVENT THE CONTRACTOR IS REQUIRED TO REMOVE AN EXISTING GATE OR PORTION OF THE AOA FEND BADGED AND APPROVED BY THE AIRPORT OPERATIONS MANAGER TO POSITIVELY CONTROL THE OPENING UN OPERATIONS CENTER. UNDER NO CIRCUMSTANCES WILL THE CONTRACTOR BE PERMITTED TO LEAVE AN OPI
OYEES. ANY REQUIREMENT REFERENCE	13.	 LICENSED VEHICLES ARE REQUIRED TO DISPLAY THE FOLLOWING SAFETY & SECURITY ITEMS IN ACCORDANCI SIGNS: COMPANY SIGNS ARE REQUIRED AT ALL TIMES. COMPANY SIGNS MUST BE AFFIXED TO BOTH SID CONTRASTING COLOR, BE A MINIMUM OF 200 SQUARE INCHES, AND BE APPROVED BY THE AIRPORT. BEACONS: BEACONS ARE REQUIRED AT ALL TIMES. A SINGLE BEACON SHALL BE AFFIXED TO THE UPPERI YELLOW/AMBER ROTATING LIGHTS VISIBLE FROM ANY DIRECTION, INCLUDING THE AIR. FLAGS: CONSTRUCTION WARNING FLAGS ARE NOT REQUIRED FOR LICENSED VEHICLES THAT ARE IN CON PROPERLY EQUIPPED TO OPERATE IN THE AOA WITH SIGNS AND A BEACON.
OR ELECTS TO EXCEED THIS HEIGHT, PRIOR TO STARTING CONSTRUCTION IS AND APPROVAL OF THE REQUEST IS	14.	 ESCORTED VEHICLES/EQUIPMENT ARE REQUIRED TO DISPLAY THE FOLLOWING SAFETY & SECURITY ITEMS IN FLAGS: CONSTRUCTION WARNING FLAGS ARE REQUIRED AT ALL TIMES FOR ESCORTED VEHICLES/EQUIPI INCLUDE BUT ARE NOT LIMITED TO HAUL TRUCKS, CONTRACTOR/SUBCONTRACTOR VEHICLES, SELF-PRO FLAGS SHALL BE AFFIXED TO BOTH SIDES OF THE UPPERMOST PART OF THE VEHICLE/EQUIPMENT, BE A CHECKERED PATTERN, AND HAVE PATTERN SQUARES THAT ARE 1-FOOT BY 1-FOOT, VISIBLE FROM BOTH FLAGS ARE NOT REQUIRED.
D ATTENDEES WILL INCLUDE PROJECT RK OCCURRING DURING THE CURRENT	STO	OCKPILED MATERIAL
NGS.	1.	DEMOLISHED MATERIAL SHALL BECOME PROPERTY OF THE CONTRACTOR UPON LEAVING THE AOA FENCE. C WASTE AT MCKELLAR PARK WITH AIRPORT APPROVAL.
HE FIELD FOREMAN WHO WILL BE IN	2.	CONTRACTOR TO MANAGE STOCKPILES SO THAT THEY DO NOT ATTRACT WILDLIFE. CONTRACTOR TO MANA
REMAN ON-SITE OR IMMEDIATELY IE CONTRACTOR AND	3.	STOCKPILES SHALL BE NO CLOSER THAN 10 FEET TO A SECURITY FENCE.
NAGER FOR THE DAYS WORK.	WIL	DLIFE MANAGEMENT
DSURES AND CONSTRUCTION EFFORTS	1.	FOOD SCRAPS MUST BE COLLECTED FROM CONSTRUCTION PERSONNEL ACTIVITY.
	2.	ANY ACTIVITY TAKING PLACE THAT CREATES A STANDING BODY OF WATER MUST BE REMEDIED WITHIN 24 H
NOTAMS RELATED TO THE PROJECT CILITY IMPACTS.	3.	MOWING SCHEDULES HAVE BEEN ESTABLISHED TO MAINTAIN, WHEN POSSIBLE, A HEIGHT OF 6 TO 10 INCHES BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAINTAIN A MAXIMUM GRASS HEIGHT OF 10 INCHES WITH ANTICIPATED TO OCCUR ON THIS PROJECT.
	FOR	REIGN OBJECT DEBRIS (FOD)

- 1.FOREIGN OBJECT DEBRIS AT AIRPORTS INCLUDES ANY OBJECT FOUND IN AN INAPPROPRIATE LOCATION THAHE AIRPORT.ON CONSTRUCTION SITES FOD TYPICALLY IS COMPRISED OF LOOSE GRAVEL, BLOWING SAND, WIRE BRISTLESEIR WORKPACKAGING.
 - 2. THE PRESENCE OF FOD ON AN AIRPORT'S AOA POSES A SIGNIFICANT THREAT TO THE SAFETY OF AIR TRAVEL. CRITICAL PHASES OF FLIGHT, WHICH CAN LEAD TO CATASTROPHIC LOSS OF LIFE AND AIRFRAME, AND AT THE

METHODS OF FOD CONTROL:

- 1. CONTRACTOR SHALL PROVIDE TRAINING TO ALL EMPLOYEES WORKING WITHIN THE AOA ON EFFECTIVE FOD CONSEQUENCES OF FOD, FOD AWARENESS, AND GOOD HOUSEKEEPING PROCEDURES.
- 2. PREVENTING FOD FROM OCCURRING IS THE MOST EFFECTIVE FORM OF FOD MANAGEMENT. CONTRACTOR MU DEVELOP A PLAN TO PREVENT FOD FROM OCCURRING. TYPICAL FOD PREVENTION MEASURES INCLUDE THE U TOLERANCE OF LITTERING, AND TYING DOWN ITEMS WHICH MAY BE EASILY WIND BLOWN.
- 3. CONTRACTOR MUST IMMEDIATELY REMOVE ANY DEBRIS FROM ACTIVE AIRFIELD AND HAUL ROUTE PAVEMENT
- 4. CONTRACTOR MUST ACTIVELY IMPLEMENT DUST CONTROL MEASURES TO MINIMIZE THE AMOUNT OF DUST O AND STORAGE AREAS. DUST ON THE AIRFIELD PAVEMENTS WILL NOT BE TOLERATED. IF PROPER MEASURES A STOPPED UNTIL PROPER MEASURES ARE IMPLEMENTED.

	PREPARED F	OR:		
T ALL TIMES. AT A MINIMUM, PAVEMENTS SHALL BE SWEPT AT THE END	K	lom		mus Ic
RUNWAY OBSTACLE FREE ZONE OF ANY ACTIVE RUNWAY WITHOUT ACLE FREE ZONE EXTENDS TO 250' FROM THE CENTERLINE OF ANY		ERNATION	IAL AIRP	ORT
T BOARDING BRIDGES. FOLLOW POSTED SPEED LIMIT SIGNS AND DO NOT ID PROPERTY DAMAGE TO AIRPORT OPERATIONS. DRIVE ONLY ON	PREPARED B	Y:		
STRUCTION AREAS. DURING NON-CONSTRUCTION PERIODS, THE REA.		FC	th	
D PHASING PLANS. NO PERSON SHALL ENTER THE AOA, OR ANY OTHER ESCORT. CONTRACTOR OPERATIONS WITHIN THE AOA ARE LIMITED TO ERSONNEL MUST NOT LEAVE THE PROJECT AREAS AT ANY TIME	KEY MAP:			
CTOR VEHICLES AND EQUIPMENT ARE ALLOWED INSIDE OF THE PROJECT R THAN 10 FEET FROM ANY SECURITY FENCE.				
ADWAYS AND HAUL ROUTES TO THE PROJECT WORK AREA THROUGH THE TO THE HAUL ROUTES SHOWN. CONTRACTOR IS RESPONSIBLE FOR ANY Y PERFORM CONSTRUCTION ACTIVITIES, UNLESS SHOWN OTHERWISE ON JL ROUTES AND STAGING AND STORAGE AREAS TO THEIR ORIGINAL				
IAL NECESSITY AND WHO HAVE BEEN BADGED AND APPROVED BY THE DEFINED IN THE PROJECT PHASING PLANS THE CONTRACTOR MUST HE PROJECT WORK AREA MUST BE ESCORTED BY BADGED PERSONNEL. IGS.	ESCRIPTION			
IE CONTRACTOR SHALL PROVIDE SECURITY FOR THESE AREAS. THE BARRICADES, AND OTHER MEANS TO BE TAKEN TO SECURE SCHEDULED RPORT PROVIDES SECURITY OVERSIGHT AND PATROLS OF THE AIRPORT,	BY			
A FENCE, THE CONTRACTOR MUST PROVIDE PERSONNEL WHO ARE	DATE			
ING UNTIL IT HAS BEEN RE-SECURED AND INSPECTED BY THE IN OPENING IN THE AOA FENCE AT THE END OF A WORK DAY.	ON N			
DANCE WITH THE LATEST VERSION OF FAA AC 150/5210-5: TH SIDES OF THE VEHICLE, INCLUDE THE COMPANY LOGO IN A T.				
PPERMOST PART OF EACH VEHICLE. BEACONS SHALL BE				
N CONSTANT TWO-WAY RADIO COMMUNICATION WITH THE ATCT AND				
MS IN ACCORDANCE WITH THE LATEST VERSION OF FAA AC 150/5210-5: EQUIPMENT. ESCORTED VEHICLES/EQUIPMENT REQUIRING FLAGS F-PROPELLED MACHINERY, AND MISCELLANEOUS MOTORIZED EQUIMENT. , BE A MINIMUM OF 3-FOOT BY 3-FOOT WITH AN ORANGE AND WHITE BOTH SIDES. WHEN A BEACON IS PRESENT CONSTRUCTION WARNING	ERVICE ROAD AL AIRPORT		Y & PHASING -	
ICE. CONTRACTOR SHALL HAUL DEMOLISHED MATERIAL OFF SITE OR	ICLE SI ATION/ HIS. TN		AFET	
MANAGE STOCKPILES SO THAT THEY DO NOT CREATE FOD.	ABILITATE VEH EMPHIS INTERN MEMP		RUCTION S/	
N 24 HOURS.	RE		ISN	
NCHES, TO HELP PREVENT WILDLIFE FROM BECOMING A HAZARD. IT WILL S WITHIN THE CONSTRUCTION WORK AREA. THIS ITEM IS NOT			00	
N THAT CAN DAMAGE AIRCRAFT, EQUIPMENT, OR AIRPORT PERSONNEL. STLES FROM SWEEPER HEADS, FOOD WRAPPERS, OR MATERIAL				
RAVEL. FOD HAS THE POTENTIAL TO DAMAGE AIRCRAFT DURING AT THE VERY LEAST INCREASED MAINTENANCE AND OPERATING COSTS.	Line and Lin	SHUA T.		
E FOD MANAGEMENT. TRAINING SHALL INCLUDE DESCRIPTION AND	Multin Still	AGRICULTUR		025
TOR MUST MONITOR CONSTRUCTION ACTIVITIES AND PROACTIVELY THE USE OF COVERED TRASH CONTAINERS, COVERED LOADS, ZERO	DESIGNED	DRAWN		KED.
EMENTS THAT RESULTS FROM CONSTRUCTION ACTIVITY.	PROJECT NO	<u>WUH</u> 0: 0024M300		M
DUST ORIGINATING FROM THE WORK AREA, HAUL ROUTES, AND STAGING	PRINT DATE	: 4/7/2025 SHEET NO).	
URES ARE NOT IMPLEMENTED TO CONTROL DUST, WORK WILL BE	0	GC1.0	00	

PHA	SING NOTES:						
1.	THE CONTRACTOR MUST OF CLOSURE WILL BE PERMIT	COMPLETE THE PROJECTED FOR INSTALLATION BE ALLOCATED TO AC	CT WITHIN 30 CALEN N OF PERMANENT PA COMPLISH AA1 WOF	DAR DAYS. AN ADDI VEMENT MARKING K IF AWARDED.	TIONAL 2 DAY S IN PHASE 4.	<u> </u>	5109
2.	A CALENDAR DAY IS DEFIN HOLIDAYS, AND NON-WORI EFFECTIVE DATE IN THE NO	ED AS ANY DAY ON TH K DAYS. CONTRACT TIN DTICE TO PROCEED.	E CALENDAR. IT INCL /IE BASED ON CALENI	UDES SATURDAYS, DAR DAYS WILL BEG	SUNDAYS, IN ON THE		30P
3.	NIGHT OPERATIONS ARE N OPERATIONS MUST FIRST PROJECT ENGINEER.	OT ANTICIPATED ON T BE COORDINATED WITH	HIS PROJECT. ANY IN I AND OBTAIN WRITT	IPLEMENTATION OI EN APPROVAL FRO	⁼ NIGHT M THE MSCAA	+	
4.	LIQUIDATED DAMAGES WIL CONTRACT TIME FOR INDIV UP TO \$500 PER DAY.	L BE ASSESSED FOR TH	HE REQUIREMENTS D UB-PHASES WILL BE \$	ESCRIBED IN THE SI SUBJECT TO LIQUID	PECIFICATIONS. ATED DAMAGES	42I -	
5.	ALL PHASES AND/OR SUB- CONTRACTOR WISHES TO COORDINATE WITH AND OF	PHASES ARE TO BE CO COMBINE PHASES OTH BTAIN WRITTEN APPRC	MPLETED AS DESCRI IER THAN AS NOTED IVAL FROM THE MSC	BED ON THIS SHEET BELOW, THEY MUST AA PROJECT ENGIN	. IF THE FIRST EER.	ATON *	
6.	PHASING AND SUB-PHASIN DEVIATIONS TO THE PHAS COORDINATION AND APPR BE NEEDED TO ACCOMMOI WILL BE MADE FOR THE AD	IG LIMITS SHOWN ARE E AND/OR SUB-PHASE OVAL FROM THE MSCA DATE CHANGES TO PHA DITIONAL REQUIRED B	APPROXIMATE. ANY WORK AREAS OR DUR AA PROJECT ENGINEE ASING AND WORK AR ARRICADES.	PROPOSED CHANG ATIONS MUST HAV R. ADDITIONAL BAF EAS. NO ADDITIONA	ES OR E PRIOR RRICADES MAY AL PAYMENT		
7.	THE CONTRACTOR MUST OF MUST SUBMIT A PROPOSE PRECONSTRUCTION MEET SCHEDULING PROGRESS M	COORDINATE ALL OPER D SCHEDULE AT LEAST ING. THE SCHEDULE MU IEETINGS.	ATIONS WITH THE M FIVE (5) CALENDAR I JST BE UPDATED ON	SCAA PROJECT ENO DAYS PRIOR TO THE A WEEKLY BASIS PI	GINEER AND RIOR TO		
8.	THE MSCAA PROJECT ENG DAY TO ALLOW FOR SCHEE	INEER MUST BE PROVI DULING OF PERSONNEL	DED A MINIMUM OF 4 . FOR OBSERVATION /	18 HOURS NOTICE T AND TESTING.	O ANY WORK		
9.	STAGING AREAS SHOWN O DETERMINE THE FINAL LOO STORAGE AND SECURITY O	N THE PLANS ARE APP CATION AND SIZE IN TH OF THEIR MATERIALS.	PROXIMATE. THE MSC IE FIELD. THE CONTR	AA PROJECT ENGIN ACTOR IS RESPONS	NEER WILL IBLE FOR		
	UGE			UGE			
	TSA			TSA			
			· · · ·	TAXIW	ΔΥΔ		
	AZT	TSA	· · · · · · · · · · · · · · · · · · ·	421	— TSA —		VSI
	•						
					4		
							•
				APRO			
\$							
						â	* * 1
							• •
/							
\searrow							
(
							I
					WINCHES	ER RD	• • •
		I					



	LI	EGEND					
EXISTING	PROPOSED		PREP	ARED BY:	Fo		h
		PAVEMENT - ASPHALT (BASE BID)	KEY N	IAP:			T.
N/A		PAVEMENT - ASPHALT (ADD. ALT. 1)					
2808	N/A	RIPRAP					
N/A	[///////	STAGING AREA					
N/A		PHASE 1 - BASE BID LIMITS				-	
N/A		PHASE 1 - ADD. ALT. 1 LIMITS	:				
N/A		PHASE 2 - BASE BID LIMITS					
N/A		PHASE 2 - ADD. ALT. 1 LIMITS	DESCRIP				
N/A		PHASE 3 - BASE BID LIMITS	٦				
N/A		PHASE 3 - ADD. ALT. 1 LIMITS	Ë				
N/A		PHASE 4 - BASE BID LIMITS	0 DA				
N/A		PHASE 4 - ADD. ALT. 1 LIMITS	2				
— RSA ———	N/A	RUNWAY SAFETY AREA					
— ROFA ———	N/A	RUNWAY OBJECT FREE AREA					
— TSA ———	N/A	TAXIWAY SAFETY AREA	0				
— TOFA ———	N/A	TAXIWAY OBJECT FREE AREA	ROAL	PORT			
N/A	· · ·	HAUL ROUTE	RVICE	l airi		2	
N/A	<u> </u>	LOW PROFILE BARRICADE	LE SE	liona S, TN			, , ■
N/A	1917110	MEDIUM PROFILE BARRICADE	/EHIC	ERNA MPHI:		יל אשר VERV	1 1 1 1
N/A	A	TRAFFIC CONTROL CONE	ATE ∖	S INTE ME)
	N/A	STORM SEWER	ABILIT	MPHI			
-ж	N/A	AIRFIELD FENCE	REH,	ME			
		PAVEMENT MARKINGS				5	

AIRFIELD PHASING CLOSURES					
HASE	DURATION	CLOSURES			
IASE 1	10 DAYS	VSR EAST			
ASE 2	10 DAYS	VSR WEST			
ASE 3	10 DAYS	TAXIWAY A EAST APRON CONNECTOR			
NT.	30 DAYS	OPEN - NO CONSTRUCTION			
ASE 4 2 DAYS TAXIWAY A EAST APRON CONNECTOR (INT.) VSR SINGLE LANE CLOSURES					
E: PHASE 4 SHALL CONSIST OF FINAL MARKINGS ONLY WITH					

NOTE: PHASE 4 SHALL CONSIST OF FINAL MARKINGS ONLY WITH INTERMITTENT SINGLE LANE CLOSURES TO ALLOW PAINT CURING. SHEET NO.

DESIGNED:
WUHDRAWN:
WUHCHECKED:
JTMPROJECT NO: 0024M300.10

PRINT DATE: 4/7/2025



ILE: C:\PW_WORKDIR\PW_IE\FVD_WUH\D0826740\GC2.00-CSPP.DWG Layout: CSPP-P1 By: HALEY,

		0 100 200 scale feet	PREP		RINATIC			IS ORT
	LI	EGEND	PREPA	ARED BY:				
EXISTING	PROPOSED	PAVEMENT - ASPHALT (BASE BID)			F (DI		
		PAVEMENT - ASPHALT (ADD. ALT. 1)	KEY N	IAP:				_
	N/A	RIPRAP						
N/A	<i>\</i>	STAGING AREA						<u> </u>
N/A		PHASE 1 - BASE BID LIMITS						
N/A		PHASE 1 - ADD. ALT. 1 LIMITS					1	
N/A		PHASE 2 - BASE BID LIMITS	Z					
N/A		PHASE 2 - ADD. ALT. 1 LIMITS	REVISION					
N/A		PHASE 3 - BASE BID LIMITS						
N/A		PHASE 3 - ADD. ALT. 1 LIMITS	BY					
N/A		PHASE 4 - BASE BID LIMITS	DATE					
N/A		PHASE 4 - ADD. ALT. 1 LIMITS	NO					
	∟ N/A	RUNWAY SAFETY AREA						
— ROFA ———	N/A	RUNWAY OBJECT FREE AREA						
— TSA ———	N/A	TAXIWAY SAFETY AREA				- 57		
— TOFA ———	N/A	TAXIWAY OBJECT FREE AREA	ROAD	ORT		IISAI		
N/A		HAUL ROUTE	VICE	AIRP		& PF		
N/A		LOW PROFILE BARRICADE	E SER	, TN		ETY	~ -	
N/A	(5) (5) (5) (5) (5) (5) (5) (5) (5) (5)	MEDIUM PROFILE BARRICADE	EHICL	RNATI APHIS		SAF	HASE	
N/A	A	TRAFFIC CONTROL CONE	ATE VI	MEN		NO	đ	
	N/A	STORM SEWER	BILIT	APHIS		UCT		
	N/A	AIRFIELD FENCE	REHA	MEN		ISTR		
		PAVEMENT MARKINGS				CON		

AIRFIELD PHASING CLOSURES				
HASE	DURATION	CLOSURES		
ASE 1	10 DAYS	VSR EAST		
ASE 2	10 DAYS	VSR WEST		
ASE 3	10 DAYS	TAXIWAY A EAST APRON CONNECTOR		
NT.	30 DAYS	OPEN - NO CONSTRUCTION		
ASE 4	2 DAYS (INT.)	TAXIWAY A EAST APRON CONNECTOR VSR SINGLE LANE CLOSURES		
: PHASE 4 SHALL CONSIST OF FINAL MARKINGS ONLY WITH				

DESIGNED: DRAWN: CHECKED: WUH WUH JTM

SHEET NO.

GC2.01

PROJECT NO: 0024M300.10

PRINT DATE: 4/7/2025

NOTE: PHASE 4 SHALL CONSIST OF FINAL MARKINGS ONLY WITH INTERMITTENT SINGLE LANE CLOSURES TO ALLOW PAINT CURING.



			F	PREPA	RED FOR			
		0 100 200 scale feet	, and a	ð	M			S DRT
	L	EGEND		PREPA	RED BY:			
EXISTING	PROPOSED	PAVEMENT - ASPHALT (BASE BID)						
		PAVEMENT - ASPHALT (ADD. ALT. 1)						-
8080	N/A	RIPRAP						
N/A	<u> //////</u> //////////////////////////////	STAGING AREA						
N/A		PHASE 1 - BASE BID LIMITS						
N/A		PHASE 1 - ADD. ALT. 1 LIMITS		=			ł	
N/A		PHASE 2 - BASE BID LIMITS		LION				
N/A		PHASE 2 - ADD. ALT. 1 LIMITS		DESCRIP				
N/A		PHASE 3 - BASE BID LIMITS		Β				
N/A		PHASE 3 - ADD. ALT. 1 LIMITS		ATE				
N/A		PHASE 4 - BASE BID LIMITS		DN D				
N/A		PHASE 4 - ADD. ALT. 1 LIMITS						
RSA	N/A	RUNWAY SAFETY AREA						
— ROFA ———	N/A	RUNWAY OBJECT FREE AREA						
— TSA ——	N/A	TAXIWAY SAFETY AREA		Q	_	SING		
— TOFA ———	N/A	TAXIWAY OBJECT FREE AREA		E ROA	RPORT	HAS		
N/A		HAUL ROUTE		ERVIC	AL AIR	<u> </u>		
N/A	<u>.</u>	LOW PROFILE BARRICADE		CLE SE	IS, TN	FET	SE 2	
N/A	122222	MEDIUM PROFILE BARRICADE		VEHIC	ERNA EMPH	N SA	HA	
N/A	A	TRAFFIC CONTROL CONE		TATE				
	N/A	STORM SEWER		HABILI	EMPH	-RUC		
—ж———	N/A	AIRFIELD FENCE		REF	Σ	LSN		
		PAVEMENT MARKINGS				00		

AIRFIELD PHASING CLOSURES				
IASE	DURATION	CLOSURES		
ASE 1	10 DAYS	VSR EAST		
ASE 2	10 DAYS	VSR WEST		
ASE 3	10 DAYS	TAXIWAY A EAST APRON CONNECTOR		
NT.	30 DAYS	OPEN - NO CONSTRUCTION		
ASE 4	2 DAYS (INT.)	TAXIWAY A EAST APRON CONNECTOR VSR SINGLE LANE CLOSURES		
: PHASE 4 SHALL CONSIST OF FINAL MARKINGS ONLY WITH				

DESIGNED: DRAWN: CHECKED: WUH WUH JTM

SHEET NO.

GC2.02

PROJECT NO: 0024M300.10

PRINT DATE: 4/7/2025

NOTE: PHASE 4 SHALL CONSIST OF FINAL MARKINGS ONLY WITH INTERMITTENT SINGLE LANE CLOSURES TO ALLOW PAINT CURING.

- PHASE WORK WILL CONSIST OF ASPHALT MILLING, ELECTRICAL MODIFICATIONS (PROTECTION), UTILITY MODIFICATIONS (PROTECTION), ASPHALT SURFACE COURSE, SHOULDER GRADING IMPROVEMENTS, AND TEMPORARY PAVEMENT MARKINGS.
- 2. DURING THIS PHASE THE CONTRACTOR SHALL ENTER THE AIRFIELD THROUGH CONSTRUCTION ACCESS GATE FX-WIN-1 BY THE SOUTHEAST OF THE MAINTENANCE APRON OFF WINCHESTER RD.
- 3. THIS PHASE REQUIRES CLOSURES OF THE TAXIWAY A EAST APRON CONNECTOR AND A NORTHEAST PORTION OF THE VSR WEST 2 LANES. THIS CLOSURE WILL REQUIRE THE NORTHEAST AND SOUTHWEST PORTIONS OF THE VSR TO OPERATE AS A 2-LANE ROAD FOR THE DURATION OF THIS PHASE. THROUGH ACCESS FOR ALL CONNECTORS SHALL BE MAINTAINED AT ALL TIMES.
- 4. CONTRACTOR SHALL CONFIRM THE MSCAA HAS THE NOTAM CLOSING THE WORK AREA PRIOR TO PLACEMENT OF BARRICADES. ALL BARRICADES SHALL BE PLACED PRIOR TO BEGINNING ANY CONSTRUCTION ACTIVITIES. CONTRACTOR SHALL COORDINATE WITH ALL PERSONNEL THAT THE BARRICADES DELINEATE WORK AREAS AND CLEARLY IDENTIFY LOCATIONS CONTRACTOR PERSONNEL SHALL NOT CROSS/ENTER DURING CONSTRUCTION ACTIVITIES UNLESS ESCORTED BY MSCAA APPROVED PERSONNEL.
- 5. THE CONTRACTOR SHALL PROVIDE APPROVED ESCORTS TO CONTROL CONSTRUCTION PERSONNEL AND EQUIPMENT WHEN TRAVELING ON ANY OPEN AIRFIELD PAVEMENT. ALL AIRCRAFT AND AIRPORT VEHICLES SHALL HAVE THE RIGHT OF WAY AT ALL TIMES.
- 6. PLAN SHEET BARRICADES ARE SHOWN FOR LOCATION REFERENCE ONLY. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SUPPLY ADEQUATE BARRICADES TO COMPLY WITH THE SPACING REQUIREMENTS HEREIN.
- NO CONSTRUCTION EQUIPMENT OR MATERIAL STOCKPILES SHALL BE LEFT OVERNIGHT WITHIN ACTIVE 7 AREAS.
- TEMPORARY PAVEMENT MARKINGS SHALL BE INSTALLED NO SOONER THAN 24 HOURS AFTER SEALANT 8. AND/OR SURFACE COURSE INSTALLATION.

RUNWAY 9-27 1/2 TOFA 142.5' XIWA -PI CONTRACTOR SHALL MILL & OVERLAY A MAXIMUM **TAXIWAY A** ⁶ OF 2 LANES AT A TIME TO ALLOW THROUGH TRAFFIC ON THE VSR. UTILIZE TRAFFIC CONTROL CONES FOR TRAFFIC CHANNELIZATION ON ONLY THIS PORTION OF THE VSR DURING THIS PHASE. **TEMPORARY LOW-PROFILE** -BARRICADES OR TRAFFIC A21 —— CONTROL CONES LOCATED OUTSIDE OF ACTIVE TOFA'S ALAAA └─ PHASE 3 SURFACE COUSE SHALL BE PAVED AS A SINGLE CONTINUOUS COURSE FOR EACH LANE. - SEE CSPP OVERVIEW SHEET FOR HAUL INFORMATION



			Τ	PREPA	ARED FOR	:			
		0 100 200 scale feet		گ					
	LI	EGEND		PREPA	ARED BY:				
EXISTING	PROPOSED	PAVEMENT - ASPHALT (BASE BID)		KEY M	AP:				
		PAVEMENT - ASPHALT (ADD. ALT. 1)							
18080	N/A	RIPRAP							
N/A	<u> </u>	STAGING AREA							
N/A		PHASE 1 - BASE BID LIMITS							
N/A		PHASE 1 - ADD. ALT. 1 LIMITS		=				×	
N/A		PHASE 2 - BASE BID LIMITS		ON TION					
N/A		PHASE 2 - ADD. ALT. 1 LIMITS		DESCRIP					
N/A		PHASE 3 - BASE BID LIMITS		BY					
N/A		PHASE 3 - ADD. ALT. 1 LIMITS		ATE					
N/A		PHASE 4 - BASE BID LIMITS		ON N					
N/A		PHASE 4 - ADD. ALT. 1 LIMITS							
RSA	N/A	RUNWAY SAFETY AREA							
	N/A	RUNWAY OBJECT FREE AREA							
TSA	N/A	TAXIWAY SAFETY AREA		Q	_		SING		
— TOFA ———	N/A	TAXIWAY OBJECT FREE AREA		E ROA	RPORT		HAS		
N/A	<u> </u>	HAUL ROUTE		ERVIC	AL AIF		/ & F		
N/A	<u></u>	LOW PROFILE BARRICADE		CLE SI	TION/ IIS, TN		FET	ЭЕ 3	
N/A	(1777-179)	MEDIUM PROFILE BARRICADE		VEHIC	ERNA EMPH		N SA	HA	
N/A	A	TRAFFIC CONTROL CONE		ITATE					
	N/A	STORM SEWER		HABIL	EMPH		L RUC		
—ж———	N/A	AIRFIELD FENCE		RE	Σ		LSN		
		PAVEMENT MARKINGS					2		

AIRFIELD PHASING CLOSURES					
HASE	DURATION	CLOSURES			
ASE 1	10 DAYS	VSR EAST			
ASE 2	10 DAYS	VSR WEST			
ASE 3	10 DAYS	TAXIWAY A EAST APRON CONNECTOR			
NT.	30 DAYS	OPEN - NO CONSTRUCTION			
ASE 4	2 DAYS (INT.)	TAXIWAY A EAST APRON CONNECTOR VSR SINGLE LANE CLOSURES			
E: PHASE 4 SHALL CONSIST OF FINAL MARKINGS ONLY WITH					

DESIGNED: DRAWN: CHECKED: WUH WUH JTM PROJECT NO: 0024M300.10 PRINT DATE: 4/7/2025 SHEET NO. GC2.03



ILE: C:\PW_WORKDIR\PW_IE\FVD_WUH\D0826740\GC2.00-CSPP.DWG Layout: CSPP-P4 By: HALEY, WILI

			PREP	ARED FOF	<u>}:</u>			
		0 100 200 scale feet	Ľ		en RNATIC			ORT
	L	EGEND	PREP	ARED BY:				
EXISTING	PROPOSED	PAVEMENT - ASPHALT (BASE BID)	KEY N					
		PAVEMENT - ASPHALT (ADD. ALT. 1)						
8.8.8	N/A	RIPRAP						
N/A	[///////	STAGING AREA						
N/A		PHASE 1 - BASE BID LIMITS						
N/A		PHASE 1 - ADD. ALT. 1 LIMITS	:				ł	
N/A		PHASE 2 - BASE BID LIMITS	ON TION					
N/A		PHASE 2 - ADD. ALT. 1 LIMITS	DESCRIP					
N/A		PHASE 3 - BASE BID LIMITS	BΥ					
N/A		PHASE 3 - ADD. ALT. 1 LIMITS	DATE					
N/A		PHASE 4 - BASE BID LIMITS	ON					
N/A		PHASE 4 - ADD. ALT. 1 LIMITS						
RSA	N/A	RUNWAY SAFETY AREA						
RDFA	N/A	RUNWAY OBJECT FREE AREA				I		
	N/A	TAXIWAY SAFETY AREA	Q	L		SING		
TOFA	N/A	TAXIWAY OBJECT FREE AREA	CE ROA	RPORI		PHA		
N/A	···	HAUL ROUTE	ERVIC	AL AI		≺ &		
N/A	<u></u>	LOW PROFILE BARRICADE	ICLE SI	ATION. HIS, TN		AFET	SE 4	
N/A	(22222)	MEDIUM PROFILE BARRICADE	VEH	EMPI		N S/	AHC	
N/A	A	TRAFFIC CONTROL CONE	ІТАТЕ	LNI SIH		CTIO		
	N/A	STORM SEWER	ABIL	EMPI		L RU		
)#(N/A	AIRFIELD FENCE	RE	Σ		LSNO		
		PAVEMENT MARKINGS				Ũ		

AIRFIELD PHASING CLOSURES				
HASE	DURATION	CLOSURES		
ASE 1	10 DAYS	VSR EAST		
ASE 2	10 DAYS	VSR WEST		
ASE 3	10 DAYS	TAXIWAY A EAST APRON CONNECTOR		
NT.	30 DAYS	OPEN - NO CONSTRUCTION		
ASE 4 2 DAYS TAXIWAY A EAST APRON CONNECTOR (INT.) VSR SINGLE LANE CLOSURES				
E: PHASE 4 SHALL CONSIST OF FINAL MARKINGS ONLY WITH				

NOTE: PHASE 4 SHALL CONSIST OF FINAL MARKINGS ONLY WITH INTERMITTENT SINGLE LANE CLOSURES TO ALLOW PAINT CURING. GC2.04

SHEET NO.

DESIGNED: DRAWN: CHECKED: WUH WUH JTM

PROJECT NO: 0024M300.10

PRINT DATE: 4/7/2025



NOTES:

- 1. ENGINEER APPROVED LOW-PROFILE, LOW MASS IMPACT BARRICADES SHALL BE USED FOR AIRFIELD PAVEMENT CLOSURES ADJACENT TO OR INTERSECTING ACTIVE AIRCRAFT TRAVEL ROUTES.
- 2. LOW-PROFILE BARRICADES ARE TO BE PROVIDED BY THE CONTRACTOR AND INSTALLED AT ALL CLOSED TAXIWAY LOCATIONS AS SHOWN ON THE SAFETY AND PHASING PLANS OR AS DIRECTED BY THE MSCAA PROJECT ENGINEER.
- 3. THE CONTRACTOR SHALL OBTAIN APPROVAL FROM THE MSCAA PROJECT ENGINEER FOR THE FIELD PLACEMENT OF ALL BARRICADES. LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATE.
- 4. IF THE CONTRACTOR DEVIATES FROM THE SAFETY AND PHASING PLAN, ADDITIONAL BARRICADES MAY BE NEEDED. THE CONTRACTOR SHALL GAIN APPROVAL FROM THE MSCAA PROJECT ENGINEER ON NEW BARRICADE LOCATIONS.
- 5. BARRICADES ARE TO BE INTERLOCKING AND CONTINUOUS IN ALL LOCATIONS EXCEPT FOR CONSTRUCTION PHASE ACCESS POINT. BARRICADE GAPS SHALL NOT EXCEED MINIMUM WIDTH TO GAIN VEHICLE OR EQUIPMENT ACCESS.
- THE CONTRACTOR SHALL SECURE BARRICADES BY FILLING WITH 6. WATER. LOW-PROFILE BARRICADES SHALL BE PROPERLY WEIGHTED TO PREVENT MOVEMENT BY WIND, PROP BLAST, OR JET BLAST OF UP TO 74 M.P.H.
- THE CONTRACTOR SHALL INSPECT BARRICADE LOCATIONS AND LIGHTS DAILY. THE CONTRACTOR SHALL RELOCATE AND REPLACE LIGHTS AS NEEDED FOR PROPER PLACEMENT AND FUNCTION ACCORDING TO THE PROJECT PLANS AND SPECIFICATIONS.
- 8. BARRICADES SHALL BE LOCATED OUTSIDE OF THE SAFETY AREAS OF OPEN TAXIWAYS AND RUNWAYS.
- 9. BARRICADES SHALL BE IN PLACE PRIOR TO WORK COMMENCEMENT.

01 LOW PROFILE BARRICADE SCALE: NONE

NOTES:

- 1. ENGINEER APPROVED MEDIUM PROFILE BARRICADES SHALL BE USED FOR AIRFIELD ROADWAY PAVEMENT CLOSURES.
- 2. MEDIUM PROFILE BARRICADES SHALL BE ORANGE OR WHITE.
- 3. MEDIUM PROFILE BARRICADES ARE TO BE PROVIDED BY THE CONTRACTOR AND INSTALLED AT LOCATIONS AS SHOWN ON THE SAFETY AND PHASING PLANS OR AS DIRECTED BY THE MSCAA PROJECT ENGINEER.
- 4. THE CONTRACTOR SHALL OBTAIN APPROVAL FROM THE MSCAA PROJECT ENGINEER FOR THE FIELD PLACEMENT OF ALL BARRICADES. LOCATIONS SHOWN ON THE PLANS ARE APPROXIMATE.
- 5. IF THE CONTRACTOR DEVIATES FROM THE SAFETY AND PHASING PLAN, ADDITIONAL BARRICADES MAY BE NEEDED. THE CONTRACTOR SHALL GAIN APPROVAL FROM THE MSCAA PROJECT ENGINEER ON NEW BARRICADE LOCATIONS.
- 6. BARRICADES ARE TO BE INTERLOCKING AND CONTINUOUS IN ALL LOCATIONS EXCEPT FOR CONSTRUCTION PHASE ACCESS POINT. BARRICADE GAPS SHALL NOT EXCEED MINIMUM WIDTH TO GAIN VEHICLE OR EQUIPMENT ACCESS.
- 7. THE CONTRACTOR SHALL SECURE BARRICADES BY FILLING WITH WATER. MEDIUM PROFILE BARRICADES SHALL BE PROPERLY WEIGHTED TO PREVENT MOVEMENT BY WIND, PROP BLAST, OR JET BLAST OF UP TO 74 M.P.H.
- 8. THE CONTRACTOR SHALL INSPECT BARRICADE LOCATIONS AND LIGHTS DAILY. THE CONTRACTOR SHALL RELOCATE AND REPLACE LIGHTS AS NEEDED FOR PROPER PLACEMENT AND FUNCTION ACCORDING TO THE PROJECT PLANS AND SPECIFICATIONS.
- 9. BARRICADES SHALL BE LOCATED OUTSIDE OF ALL SAFETY AREAS.
- 10. BARRICADES SHALL BE IN PLACE PRIOR TO WORK COMMENCEMENT.



02 MEDIUM PROFILE BARRICADE SCALE: NONE

- INTERLOCKING COUPLING

PREPARED FOR:						
KEY MAP:	Foth					
DATE BY REVISION DESCRIPTION						
REHABILITATE VEHICLE SERVICE ROAD MEMPHIS INTERNATIONAL AIRPORT MEMPHIS, TN	CONSTRUCTION SAFETY & PHASING - DETAILS					
DESIGNED: DRAWN: CHECKED: WUH DRAWN: CHECKED: WUH DRAWN: CHECKED: JTM						
PRINT DATE: 4/ S G(7/2025 HEET NO. C3.01					



FILE: C:\PW_WORKDIR\PW_IE\FVD_WUH\D0826740\CD1.00-DEMO.DWG Layout: CD1.01 By: HALEY, WIL



			PREPARED FOR:
	0	100 200	PREPARED BY:
	scale	feet	Foth
	L	EGEND	KEY MAP:
EXISTING	PROPOSED	PAVEMENT - ASPHALT (BASE BID)	
		PAVEMENT - ASPHALT (AA1)	
RSA	N/A	RUNWAY SAFETY AREA	
ROFA	N/A	RUNWAY OBJECT FREE AREA	
TSA	N/A	TAXIWAY SAFETY AREA	
TOFA	N/A	TAXIWAY OBJECT FREE AREA	REVISIO
· · · · · · · · · · · · ·	N/A	LOC/ILS CRITICAL AREA	
LS SA SAN	N/A	SANITARY SEWER	
ST STM	N/A	STORM SEWER	
	N/A	WATER	
<u> </u>	N/A	ELECTRICAL - AIRFIELD CIRCUIT	
UGE	N/A	ELECTRICAL - UNDERGROUND CABLE	
—— ж. ——— ж. ———	N/A	AIRFIELD FENCE	
		PAVEMENT MARKINGS	E ROAD RPORT

- 1. CONTRACTOR SHALL PRESERVE EXISTING UTILITIES ELEVATION, CASING, CONDUIT, AND CRIBBING/BRACING AT ANY LOCATION WHERE EXISTING UTILITIES CONFLICT WITH PROJECT WORK. ANY DAMAGE TO THE EXISTING UTILITIES THAT ARE NOT TO BE REMOVED SHALL BE CONSIDERED THE RESPONSIBILITY OF THE CONTRACTOR. THEY SHALL BE REPAIRED IMMEDIATELY AT THE CONTRACTORS EXPENSE. REPAIR METHODS SHALL BE APPROVED BY THE MSCAA PROJECT ENGINEER.
- 2. ASPHALT SURFACE COURSE SHALL BE A CONTINUOUS LIFT WITHIN EACH PHASE. WHERE TO EXISTING ASPHALT MEETS PROPOSED ASPHALT CONTRACTOR SHALL SAWCUT A CLEAN VERTICAL EDGE AND INSTALL ASPHALT COLD JOINT. ASPHALT JOINTS AT PHASE LIMITS INCLUDED.
- 3. PROPOSED ROAD EDGES SHALL MATCH EXISTING GEOMETRY.
- 4. SEE SHEET CD1.01 FOR FULL DEPTH DEMOLITION INFORMATION.
- 5. PROPOSED ASPHALT PAVEMENT SHALL INCLUDE REFLECTIVE MARKERS. SEE SHEET CM2.01 FOR DETAILS.





D FILE: C:\PW_WORKDIR\PW_IE\FVD_WUH\D0826740\C2.00-PAVE.DWG Layout: PAVE-P&P 1 By: HALEY, Wi

						- 50	100.00	27
				STORM CI	rossing V			27
	V STORM C	ROSSING	ELEC CROSSING			E	LEC CROSSING	28
			F.O. CROSSING	F.0.	CROSSING			
······································	WTR CROSSING							28
								29
MATCHING E	G							
			· · · · · · · · · · · · · · · · · · ·					
								20
								30
+50	113+0	0 +50	114+0	0 +50	115+00	+50	116+00	+50
								27
		· · · · · · · · · · · · · · · · · · ·						27
								28
				STORM CROS	SSING			
						F.O. CRC	DSSING	28
								29
								29
: : :		: : : :			: : : : : :	: : : :	: : : :	30
104+00	+50	105+00	+50	106+00	+50 107	/+00 +	+50 108-	+00
								27
								27
								28
└─ FG M/	ATCHING EG							
		F.O.	CROSSING					28
								29
								29
							······································	
· · · · · · · · · · · · · · · · · · ·								

PREPARED FOR:											
Memphis International airport											
PREF		D BY	:	F			Ì		ŀ		
KEY I	MAP	:	_						_		
REVISION DESCRIPTION											
BY											
NO DATE											
REHABILITATE VEHICLE SERVICE ROAD MEMPHIS INTERNATIONAL AIRPORT MEMPHIS, TN				PAVING PLAN & PROFILE							
AGRICULTURE OLANGERCO OLAN											
DESIGNED: WUHDRAWN: WUHCHECKED: JTMPROJECT NO: 0024M300.10PRINT DATE:4/7/2025											
SHEET NO. CP1.02											

0		5	10
sc	ale		feet
	VERTICAL	SCALE 5:	1
0		40	80
sc	ale		feet
Н	ORIZONTA	L SCALE 4	0:1



- 1. USE SEALANT MAUFACTURER'S RECOMMENDATION
- 2. SAWCUT JOINTS TO REQUIRED WIDTH AND DEPTH.

- NEW SAWCUT EDGE 6 INCHES INTO EXISTING OR PREVIOUS ASPHALT SURFACE COURSE. TACK COAT





<u>SECTION B-B</u>

TDOT STANDARD DRAWING: EC-STR-39

NOTE: THIS DETAIL IS TO BE UTILIZED FOR CURB INLETS.

01 TDOT CURB INLET & CULVERT PROTECTION (TYPE 2) SCALE: NONE

CURB INLET PROTECTION TYPE 2 GENERAL NOTES

BI CURB INLET PROTECTION (TYPE 2) IS USED TO INTERCEPT SEDIMENT AND PREVENT SEDIMENT LADEN WATER FROM ENTERING STORM SEWER SYSTEMS. THIS DEVICE IS INTENDED AS A SECONDARY SEDIMENT CONTROL MEASURE. CURB INLET PROTECTION (TYPE 2) IS USED IN AREAS WHERE PONDING IS NOT A CONCERN AND ADEQUATE AREA IS AVAILABLE FOR PONDING.

B5 PACK SAND/GRAVEL FILLED BAGS TIGHTLY TOGETHER END TO END TO ENSURE NO SEDIMENT FLOWS BETWEEN OR UNDERNEATH THE BAGS. WHERE TIGHT FIT IS UNACHIEVABLE, INSTALL GEOTEXTILE FABRIC (TYPE III) ALONG THE UPSTREAM FACE OF THE BAGS LAPPING OVER THE TOP BAGS 6 INCHES AND EXTENDING GEOTEXTILE FABRIC (TYPE III) A MINIMUM OF 18 INCHES UPSTREAM OF THE BAGS. COVER GEOTEXTILE FABRIC (TYPE III) WITH MINERAL AGGREGATE (SIZE 57) STONE WEDGE TO THE TOP OF THE BAGS.

(B6) ONLY GEOTEXTILE FABRIC (TYPE III) LISTED ON THE QUALIFIED PRODUCTS

(B7) AN OVERFLOW SPILLWAY SHALL BE PROVIDED BY LEAVING AN OPENING OF ONE SAND OR GRAVEL BAG WIDE AND HIGH AS SHOWN. STORMS GREATER THAN 2-YEAR, 24 HOUR STORM SHOULD NOT OVERTOP THE CURB.

209-09.41 CURB INLET PROTECTION (TYPE 2) PER EACH

PAYMENT SHALL INCLUDE ALL MATERIALS AND LABOR NECESSARY FOR CONSTRUCTION, MAINTENANCE, AND REMOVAL OF CURB INLET PROTECTION

(B) ANY PRODUCT LISTED ON THE QUALIFIED PRODUCTS LIST AS AN APPROVED

B10 MAINTENANCE SHALL BE PERFORMED AS NEEDED. FOR PROPER FUNCTION SEDIMENT REMOVAL SHALL BE PERFORMED CONTINUOUSLY AND/OR AFTER EVERY RAIN EVENT AND PAID FOR UNDER ITEM NUMBER 209-05, SEDIMENT







- NOTES:
- 1. ALL MARKINGS SHALL BE MEASURED AND PAID UNDER SPECIFICATION P-620.
- 2. ALL TWO SIDED REFLECTORS SHALL BE MEASURED AND PAID UNDER SPECIFICATION A-101.
- 3. VSR ROAD LANE MARKINGS SHALL BE APPLIED AS TEMPORARY AND PERMANENT MARKINGS.
- 4. TEMPORARY MARKINGS REQUIRED NO GLASS BEADS.
- 5. PERMANENT MARKINGS REQUIRE GLASS BEADS.

04 VSR ROAD MARKINGS & REFLECTOR LAYOUT SCALE: NONE

- 2. VSR STOP BAR MARKINGS SHALL BE APPLIED AS PERMANENT MARKINGS ONLY.



NOTES:

- 1. ALL MARKINGS SHALL BE MEASURED AND PAID UNDER SPECIFICATION P-620.

- 3. PERMANENT MARKINGS DO NOT REQUIRE GLASS BEADS.

2. CONNECTOR ROAD STOP BAR MARKINGS SHALL BE APPLIED AS PERMANENT MARKINGS ONLY.

03 SCALE: NONE

