

ITEM	DESCRIPTION	QTY.	UNIT
S-100-3.1	CONSTRUCTION ACCESS AND TRAFFIC CONTROL	1	LS
C-100-14.1	CONTRACTOR QUALITY CONTROL PROGRAM (CQCP)	1	LS
C-102-5.1	INSTALLATION AND REMOVAL OF SILT FENCE	130	LF
C-102-5.2	CATCH BASIN SEDIMENT TRAP	15	EA
C-102-5.3	FILTER SOCK	280	LF
C-105-6.1	MOBILIZATION	1	LS
P-151-4.1	CLEARING AND GRUBBING	440	SY
P-152-4.1	UNCLASSIFIED EXCAVATION	300	CY
P-209-5.1	CRUSHED AGGREGATE BASE COURSE	360	TONS
P-611-6.1	CONCRETE PAVEMENT REPAIRS	0	CY
P-620-5.1	RUNWAY & TAXIWAY MARKING	2,200	SF
T-904-5.1	SODDING	25,860	SY
T-905-5.1	TOPSOIL (4 INCHES THICK)	8,620	CY
L-108-5.1	NO. 8 L-824C CABLE, SOLID BLACK INSULATION	19,580	LF
L-108-5.2	NO. 8 L-824C CABLE, SOLID RED INSULATION	41,180	LF
L-108-5.3	NO. 1/0 AWG BARE COPPER GUARD WIRE	9,980	LF
L-108-5.4	SOLID NO. 6 AWG INSULATED EQUIPMENT GROUND CONDUCTOR	30,380	LF
L-109-5.1	SINGLE MODE FIBER OPTIC CABLE - 24 FIBERS	6,570	LF
L-110-5.1	2" SCHEDULE 40 PVC CONDUIT, CONCRETE ENCASED	1,750	LF
L-110-5.2	2" RIGID GALVANIZED STEEL CONDUIT, CONCRETE ENCASED, IN PAVEMENT	90	LF
L-110-5.3	4" SCHEDULE 40 PVC CONDUIT, CONCRETE ENCASED	4,990	LF
L-110-5.4	4" RIGID GALVANIZED STEEL CONDUIT, CONCRETE ENCASED	20	LF
L-110-5.5	TWO WAY 4" SCHEDULE 40 PVC CONDUIT, CONCRETE ENCASED	4,600	LF
L-110-5.6	TWO WAY 4" RIGID GALVANIZED STEEL CONDUIT, CONCRETE ENCASED	10	LF
L-110-5.7	HANDHOLE, AIRCRAFT RATED	27	EA
L-112-5.1	HORIZONTAL DIRECTIONAL DRILLING, 4" HDPE CONDUIT	4,600	LF
L-120-5.1	RWSL SHELTER NO. 1	1	LS
L-125-5.1	RUNWAY ENTRANCE LIGHT	23	EA
L-125-5.2	INSTALLATION OF 3/4" COVER PLATE	16	EA
L-125-5.3	RUNWAY ENTRANCE LIGHT IN EXISTING BASE CAN	81	EA
L-125-5.4	TAKEOFF HOLD LIGHT IN EXISTING BASE CAN	64	EA
L-130-5.1	AIRFIELD ELECTRICAL TESTING	1	LS
16-3.1	CCR INSTALLATION	3	EA
16-3.2	EARTH ELECTRODE SYSTEM	1	LS
16-3.3	INSTALLATION OF LIGHTNING PROTECTION SYSTEM	1	LS
16-3.4	UTILITY METER SERVICE, SHELTER 1	1	LS
16-3.5	UTILITY COORDINATION, SHELTER 1	1	ALW



PROGRAM MANAGER
PARSONS
 Program Management Consultant
 Parsons Transportation Group Inc.
 Project Office:
 4225 Airways Blvd.
 Memphis TN, 38116

ENGINEER
HNTB
 777 108TH AVE NE
 SUITE 1000
 BELLEVUE, WA 98004 (425) 455-3555
 WWW.HNTB.COM

JOB NO.
85091

DRAWN BY:


KLM

CHECKED BY:

CTX

APPROVED BY:

CBD



ENGINEER-SUBCONSULTANT

JOB NO.

REVISIONS

MARK	DATE	DESCRIPTION
0	12/11/2025	ISSUED FOR BID
1	02/18/2026	ADDENDUM #1

MSCAA PROJ. NO.
16-1408-01

PROJECT:
**RW 9/27 RUNWAY
 STATUS LIGHTS -
 DESIGN**

SHEET TITLE:
**SUMMARY
 OF
 QUANTITIES**

DWG. FILE NAME
161408-G-SQ-003.DWG

DATE
12/11/2025

SCALE
N.T.S.

SHEET NO.
G-SQ-003